

JCCS Services LLC
1200 Woodruff Rd, Greenville, SC 29607. SUITE B-3
camilocalle@jccs-services.com
864-9079052



Estimate

For: Bruce Ridge
Henry.Ridge@selfregional.org

Estimate No: 4273
Date: 06/25/2026

Job location Self Regional Greenwood - Behavioral Health Center - Activity Room 2

Description	Quantity	Rate	Amount
Plexiglass Protective Barrier Installation – Designated Patient Area	1	\$350.00	\$350.00

Scope of Work

Work Area Preparation

- Prepare designated area for protective barrier installation.
- Protect adjacent walls, television, millwork, flooring, and finishes during work operations.

Plexiglass Protective Barrier Installation

- Provide and install custom plexiglass protective barrier around entire television assembly.
- Fabricate barrier to field-verified dimensions to fully enclose the television and cable management area.
- Install barrier with no accessible openings or entry points, in order to prevent patient access to cables, wiring, and television mounting components for safety purposes.
- Secure barrier using appropriate mounting hardware while maintaining a clean and professional appearance.
- Ensure protective barrier allows proper visibility of the television while supporting patient safety requirements.

Fit & Finish

- Verify plexiglass barrier is securely installed, properly aligned, and free of visible defects.
- Ensure all edges are smooth, finished, and safe for occupant interaction.

Finishing & Cleanup

- Inspect completed work for quality and proper installation.
- Remove debris and materials generated during work activities.
- Leave the affected area clean, safe, and ready for use.

- Estimate 4273 - 06/25/2026

Subtotal	\$350.00
Includes TAX 0%	\$0.00
Total	\$350.00
Total	\$350.00

WhatsApp Image 2026-06-23 at 12.15.25.jpeg

